

Unitex Specifications

Unitex® Coatings Specification over Painted Masonry Walls

Substrate Details

Unitex Warranty	7 year when applied in accordance with the relevant technical specifications.
Base Coat Render	Polymer Render Wet or Dry
Applicable Texture Coating	Substrate compatible with all Unitex Texture Coatings

For detailed information on Unitex Products, Systems and Warranties, please contact:

Position: National Sales Manager
Name: Luke Molloy
Phone: 0419 114 633
Email: luke.m@unitex.com.au

Construction / Detailing

Responsibility

All works in this section shall be the responsibility of the Main Contractor, unless previously agreed in writing. Unitex Granular Marble Pty Ltd accepts no responsibility for defective workmanship in relationship to the application of the Unitex system, or for defects in the design, construction, or condition of the building, either as built or in relation to the works.

The Main Contractor is to ensure that they are fully conversant with exterior legislation requirements, the project specifications and details, current **Brickwork Specifications & Unitex** specification (www.unitex.com.au) and any specific installation requirements relating to the Main Contractors responsibilities before any works commence. If there are any substitution of products or systems, the Main Contractor is to provide Builder with Unitex written, site-specific specifications. Before any works commence, the Main Contractor is to supply on-site, a 2m² to 5m² sample of the complete system for the Builders approval for substrate adhesion, build thickness, and finish quality.

The Main Contractor is also responsible for the various subcontractors to ensure that all items relating to substrate adhesion, weather tightness, penetrations and dissimilar material junctions affecting the construction system are strictly in accordance with project specific details, manufacturer's instructions and Unitex specification details i.e. items such as roofs, soffits, openings, lights & security fittings, electrical wiring, flashings, deck membranes dissimilar junctions etc. that abut, flash or penetrate the system.

The Main Contractor shall also ensure that all work is only carried out by competent contractors able to deliver the finished Unitex System, in accordance with the project drawings, manufactures details and Unitex specification details.

Note: If the Main Contractor has the opinion that the specification is not suitable for site conditions, the Builder and Unitex must be consulted with the concerns prior to any works commencing. i.e. Specifying a non-cavity system where a cavity system would be more suitable.

Substrate Construction

The **substrate** will be expected to be installed according to manufacturers, architect and engineering specifications and shall be inspected prior to application by the Main Contractor, and any variations from specifications or requirements communicated in writing to the Builder prior to the commencement of Unitex System works.

The substrate surface must be cleaned free of any grease, oils, scaling laitance, efflorescence, form-oil compounds, mould, fungi, rust, dirt, dust or any other foreign matter. Pre-painted surfaces must be wire-brushed back to the bare substrate, or a Hatch Test performed to assess coatability.

All surfaces **MUST** be suitably prepared for the Unitex System installation.

Prior to works commencing, check the surface is level and straight in all directions. If the substrate contains expansion joints, care should be taken to ensure they are maintained.

Note: If substrate installation and quality is doubtful the **Substrate Manufacturers Representative** should be contacted for a site inspection and approval before any work is undertaken.

Preparation

If the Builder has not protected adjoining surfaces, i.e. windows and frames etc, the Main Contractor must protect all other surfaces prior to works commencing.

Scaffolding

The scaffolding must be installed according to the requirements of all local and safety authorities, providing suitable access for the Main Contractor to complete the project to the required standards.

Control Joints

All expansion, control and cosmetic joints are to be nominated by and are the responsibility of the builder. Only Builders, and the Builders nominated engineer / architect etc. and base system provider can predict likely building and surface effect movement. An allowance for more, rather than less expansion/contraction joints provides the greatest opportunity for a quality finish by the applicator and prevention of structural movement cracking. Structural movement cracking is not covered by Unitex product warranty.

Unitex[®] Coatings Process over Painted Masonry Walls

STEP 1: Base Coat

Unitex Wet or Dry Polymer Render



Application Method: Trowel

Product Coverage: 8-10 m²

Dry Coating Thickness: N/A

Drying Time: approx. 72 Hours (must achieve less than 12% WME moisture content)



1. Mix Unitex Polymer Render Wet with 5-10% Portland Cement, or Dry Polymer Render with water. Apply Unitex Wet or Dry Polymer Render to entire surface. Allow to dry to less than 12% WME

STEP 2: Base Coat

Unitex Beach or Redi-Render



Application Method: Trowel

Product Coverage: 1-6 m² (Beach) 3.5-4.5 m² (Redi-Render)

Dry Coating Thickness: Up to 10mm

Drying Time: approx. 72 Hours (must achieve less than 12% WME moisture content)



2. Apply one coat of Unitex Beach or Redi-Render to entire surface. Allow to dry to less than 12% WME. A second coat may be required to achieve desired build. Allow to dry to less than 12% WME.

STEP 3: Texture Coat

Unitex Texture Coat

Ensure coating thickness is as per product specifications



Application Method: Trowel/Float

Product Coverage: Various

Dry Coating Thickness: Various

Drying Time: approx. 72 Hours (must achieve less than 12% WME moisture content)



3. Apply one coat of your chosen Unitex Texture to entire surface and allow to dry to less than 12% WME

STEP 4: Protective Coat

Unitex PTC

Recommended 2 coats



Application Method: Brush/Roller

Product Coverage: 35-45 m²

Dry Coating Thickness: .5mm

Drying Time: approx. 48 Hours (must achieve less than 12% WME moisture content)



4. Apply a recommended minimum of two coats of Unitex coloured PTC

Unitex® Product Information, TDS and MSDS documents:

All Unitex® products are thoroughly documented, and Technical Data Sheets and Material Safety Data Sheets are available through your Unitex Technical Representative, or via the Unitex® websites: www.unitex.com.au and www.render.com.au

Disclaimer

The information contained in this specification is based on our experience, testing and certification representing the latest information at the date of documentation and is given in good faith. No responsibility is undertaken for use of this information outside of Unitex Granular Marble Pty Ltd parameters given substrates and site conditions are outside our control. Where a contractor applies Unitex Granular Marble Pty Ltd purchased products in accordance with the specifications, SDS, TDS and a Unitex Granular Marble Pty Ltd Warranty document is available when the project has been completed according to Unitex Granular Marble Pty Ltd written documentation. Unitex Granular Marble Pty Ltd reserves the right to alter or update information and formulations at any time without prior notice.

Unitex
22 Park Drive
Dandenong VIC 3175
Phone: **(03) 9768 4900**
Fax **(03) 9768 4999**
www.unitex.com.au

Unitex (NSW)
14 Artisan Road
Seven Hills NSW 2147
Phone: **(02) 9838 0911**
Fax **(02) 9838 9555**
www.unitex.com.au

URW (Oakleigh)
1346 North Road
Oakleigh VIC 3167
Phone: **1800 RENDER**
Fax **(03) 9544 3620**
www.render.com.au

URW (SA)
2/54-56 Cavan Road
Dry Creek SA 5094
Phone: **(08) 8262 7900**
Fax **(08) 8262 7922**
www.render.com.au